

Vipac Engineers & Scientists Ltd.

279 Normanby Rd, Port Melbourne, VIC 3207, Australia Private Bag 16, Port Melbourne, VIC 3207, Australia **t.** +61 3 9647 9700 | **f.** +61 3 6245 4370 | **e.** melbourne@vipac.com.au **w.** www.vipac.com.au | A.B.N. 33 005 453 627 | A.C.N. 005 453 627

CERTIFICATE OF CONFORMANCE

This Certificate is completed as the formal sign-off representing the acceptance, verification and validation of the tested hardware items (products), in accordance with AS/NZS 4994.1-2009 Section 4.1 Testing.

Project Title: Temporary Edge Protection Systems	Ref No.: 30B-13-0158
	Date: 18 Dec 2013

Customer Information:

Customer:	Aldeck Sales	
	15 Brock Street	
Address:	Thomastown	
	VIC 3074	
Contract/Purchase Order No.:	0154	

Product Information:

Guardrail System Description			Compliance
1.	Bolt On Bracket	AS/NZS 4994.1 Appendix A, B & C	
2. Perimeter Handrail System			AS/NZS 4994.1 Appendix A, B & C
3.	Clamp On Bracket	AS/NZS 4994.1 Appendix A & B	
4.	Perimeter Handrail attache Bracket	AS/NZS 4994.1 Appendix A, B & C	
5.	Perimeter Handrail attached	AS/NZS 4994.1 Appendix A, B & C	
6.	Gable End Bracket	AS/NZS 4994.1 Appendix A, B & C	
Verification Documents: Vipac test report: 30B-13-0158-TRP-3			42235-1
Quality Standard: AS/NZS 4994.1:2009 Temporary edge			protection, Section 4.1 Testing

Compliance Statement:

Vipac Engineers & Scientists certifies that the products listed have been tested in accordance with AS/NZS 4994.1:2009 *Temporary edge protection,* and comply with Section 4.1 *Testing.* Systems 1, 2, 4, 5 and 6 may be used on all roof inclinations. System 3 may be used only on roofs with an incline less than 15 degrees.

Title:	Façade Group Leader <i>(Acceptance)</i>	Group Leader – Solar Thermal Systems (Authorisation)	Project Engineer (Review/Images Added)
Name:	Michael Petrovic	Greg King	Jared Carnie
Signature:	Alex	/a la	Harnic
Date:	18 Dec 2013	18 Dec 2013	10 Jul 2017

Part of AS/NZS ISO 9001-2000 certified Quality Management System of Vipac Engineers & Scientists Ltd (Certification No. 7690).

Aldeck Sales Aldeck - Temporary rail testing Temporary Edge Protection Systems





Figure 1: Bolt On Bracket



Figure 3: Perimeter Handrail with C-Purlin Clamp



Figure 5: Deck Fixing Clamp



Figure 2: Clamp On Bracket




Figure 4: All Purpose Fixing Bracket



Figure 6: Gable End Bracket

